

REBAR FABRICATION PRODUCTS

SHEARLINES BUILT TO ORDER TO MEET YOUR NEEDS



***SLIDING GAUGE CAN BE SET TO THE INCH
SHEARLINE CAN ADAPT TO ANY TYPE OF SHEAR***

20'-30'-40'-60' Welded channel frame and legs with angle bracing. Preload holds two full bundles of rebar with optional double sided to hold four bundles. An optional four power roller system will push the rebar through the shear with the flip of a lever. The discharge racks will hold three bundles before having to unload.



get a quote fast